TUMKUR DIVISION.

ADVERTISEMENT.

The 15th September 1888.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 15th October 1888, for restoring the Chikka and Dodda Banagere Tanks, R. Nos. 171 and 175 of Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Approximate estimate of quantities for restoring the Chikka and Dodda Banagere Tanks of Sira Taluk.

Details.	Per.	Quantity.	Rate.
Bund—			
Earth work	C. Yd.	51,459	
New stone work	do	1,177	
Old stone work	do	1,681	
Boundary Mark stones	E.	2	
Grade stones	E.	97	
No. I and II sluices repairs Lump sum Rs. 150	..	..	
No. III sluice in body wall Lump sum Rs. 50.	..	..	
Left waste weir—			
Excavation	C. yd.	65	
Brick in chunam	C. ft.	2,403	
Concrete	do	555	
Chunam plastering	Sqr.	7·15	
Covering slabs	Sq. ft.	1,830	
New stone work	C. yd.	89	
Right waste weir—			
Excavation lump sum Rs. 5	..	..	
Brick in chunam	C. ft.	3,604	
Concrete	do	654	
Chunam plastering	Sqr.	15·47	
Covering slabs	Sq. ft.	2,312	
New stone work	C. yd.	112	
Distribution—			
Right sluice channel—			
Excavation	do	3,168	
Mile and ziro stones	E.	2	
Furlong stones	do	7	
Index stones	do	16	
Ordinary index stones	do	24	
Grade stones	do	48	
Miscellaneous—			
Compensation for lands submerged. Lump sum Rs. 75 ..	...	..	

4. Each tender must be accompanied by a deposit of Rs. one hundred in cash or Government promissory notes as earnest money and be superscribed "Tender for restoring the Chikka and Dodda Banagere Tanks" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

C. T. DALAL,
Executive Engineer.